

## addendum

---

**addendum no.** 01

**date:** 1/25/2019

**bid date:** 2/12/2019

**project name:** MPS Cather Switchboard Replacement

**project no:** 18358

---

This addendum is hereby made a part of the contract documents to the same extent as if it were originally included therein. Contract documents shall be considered modified or revised as hereinafter described.

### ***specifications***

1. Specifications – General and supplemental conditions:
  - a. Part 2.5 – Work Restrictions: A separate contractor will be on site for a portable classroom removal project. Portable demolition schedule is between June 4<sup>th</sup> and June 28<sup>th</sup>, 2019. Access through the driveway to the south parking and dock area may be temporarily hampered by demolition equipment during this period. Coordinate access to impacted areas with demolition contractor and MPS.
  - b. Part 2.16 – Project Schedule: Demolition of power and electrical connections to portable outlined in this addenda shall be a top priority and shall be completed no later than EOD Monday, June 3<sup>rd</sup>, 2019.
2. Drawing e1 – Electrical Plans & Riser Diagram
  - a. Remove existing 100A feeder serving portable classroom on south side of building. Remove transformer and conductors complete back to breaker (breaker to remain as spare). Remove existing below-grade conduit complete back to edge of concrete parking / sidewalk. Remove existing low voltage cabling serving portable including data network, intercom, and fire alarm. Remove low voltage conduit complete. Reprogram existing fire alarm panel (Vigilant / GE) to accommodate removal of portable. See project schedule note above about timeline for this demolition work.

***end of addendum***