



ADDENDUM NO. 2
City of Council Bluffs
Mid-America Center (MAC) Scoreboards
Council Bluffs, Iowa

HGM PROJECT # 150318A / CB# BM-19-03
DATE OF ISSUE: February 8, 2019
DATE OF BID OPENING: February 13, 2019 @ 2:00 p.m.

NOTE TO PLANHOLDERS: Please insert this addendum into your copy of the Project Contract Documents. The following additions or changes to the Contract Documents for the above-named project are issued by the Architect and have the same force and effect as though part of the original issued.

CHANGES TO PROJECT MANUAL

SECTION 10 11 00 ELECTRONIC MESSAGE BOARDS

Refer to 10 11 00-3, line 31; Add the following:

Provide mobile power box at floor level for owner's staff to mobilize LED message board regardless of location when lowered from ceiling.

Provide 150 foot power cables to run from the power box to reach the LED message board to provide power. Coordinate length of cable required, size and quantity of conductors, termination type (Cam lock, plug, receptacle, etc.) with Message Board.

Provide mobile video box at floor level for owner's staff to mobilize LED message board regardless of location when lowered from ceiling.

CHANGES TO ELECTRICAL DRAWINGS:

SHEET E1.1

Add the following:

GENERAL NOTES

1. Provide 208 3 phase power to motorized chain hoists. Verify amperage with hoist manufacturer.
2. Provide power box at hanging LED message board mounted to or inside truss with a single large power cable with easy plug in/removal ability for when system is lowered/rehung.

- 1 3. 208 volt / 125 amp 3-phase breaker exists at the catwalk.
2
3 4. 208 volt / 200 amp, 3-phase panel with 5-wire cam lock connections exists on the Arena
4 floor.
5
6 5. Provide mobile power box at floor level for owner's staff to mobilize LED message board
7 regardless of location when lowered from ceiling.
8
9 6. Provide 150 foot power cables to run from the power box to reach the LED message
10 board to provide power. Coordinate length of cable required, size and quantity of
11 conductors, termination type (Cam lock, plug, receptacle, etc.) with Message Board.
12

13 All other stipulations and requirements of the plans and specifications remain in effect. This
14 addendum shall be attached to and made part of the Contract Documents and shall be
15 acknowledged with the bidders' proposal.
16

17 Respectfully Submitted:
18 HGM ASSOCIATES INC.



19
20 Dean Fajen, P.E., A.I.A.
21 Project Manager